

General Attendance Requirements

1. 2 x 240 volt / 13amp. Alternatively, 2 x 110 volt / 32 amp electric power to the workface.
2. Use of welfare facilities.
3. All dust sensitive work areas and equipment to be screened off and covered before our commencement.
4. Use of a waste skip to deposit site debris.
5. Work areas to be free of other trades and their equipment during our installation and curing programmes.
6. Extension of daily and weekend working hours to be accommodated when necessary.
7. Areas assumed to be dry, clear and clean prior to our commencement.
8. Use of forklift truck for off-loading deliveries of materials and warm, dry storage.
9. Deliveries of materials and plant prior to our arrival to be accepted by you / your client's representative and all documentation retained for our records and handed over on our arrival.
10. Minimum ambient temperature to be maintained at 10°C during our installation and curing programmes.
11. All moveable plant and machinery to be moved prior to our arrival.
12. General standard of lighting to be maintained to approx. 300 lux.
13. Weekend working hours deemed to be 6pm Friday to 6pm Sunday unless otherwise stated.

N.B. The application of the floor finish specified overleaf will not enhance or otherwise affect the general falls / levels in the concrete base. As the finish is laid by hand minor differences in thickness may occur and depressions may

Lasercroft Ltd 9 Hedon Road
Kingston Upon Hull
East Yorkshire HU9 1LH
Telephone 01482 229 119
Email info@lasercroft.com
www.lasercroft.com

Registered in England No. 2613181
Registered Office as above
VAT Registration No. 686 7165 84

